



प.सं.:०८२/८३

च.नं.:

शिखर नगरपालिका

नगर कार्यपालिकाको कार्यालय

तलकोट, डोटी

E-Mail : shikhar municipality@gmail.com
E-Mail : int.shikhar municipality@gmail.com
Web : www.shikhar mun.gov.np

सुदूरपश्चिम प्रदेश, नेपाल

दररेट पेश गर्ने सम्बन्धी सूचना !

(सूचना नं. १/२०८२-०८३-सो.ख, मिति: २०८२/११/०५)

यस शिखर नगरपालिकाको आ.व.२०८२/०८३ को स्वीकृत वार्षिक कार्यक्रम अनुसार यस शिखर नगरपालिका अन्तर्गत ५ नं. वडामा तपसिल बमोजिमको कार्य गर्नुपर्ने भएकोले ईच्छुक निर्माण कम्पनी/व्यवसायीले तपसिल बमोजिमका शर्तहरूको आधारमा BOQ अनुसारको दररेट भरि यस कार्यालयमा पेश गर्नहुन सम्बन्धित सबैको जानकारीका लागि यो सूचना प्रकाशित गरिएको छ।

तपसिल:

क्र.सं.	कामको विवरण	जम्मा रकम (भ्याट सहित)	दररेट पेश गर्ने अन्तिम मिति
१	राधा कृष्ण मा बि को भवन निर्माण र मर्मत कार्य, तिजाली	९७१७४९.३२	२०८२/११/१२ कार्यालय समय भित्र

शर्तहरू:

- (१) दररेट पेश गर्ने कम्पनी/व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नविकरण भएको दर्ता प्रमाणपत्रको प्रतिलिपि, मु.अ.क. दर्ता प्रमाणपत्रको प्रतिलिपि र आ.व. २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्नेछ।
- (२) उक्त कार्यको लागि आवश्यक BOQ फाराम यस कार्यालयबाट रु.१,००० दस्तुर बुझाई खरिद गर्नुपर्नेछ।
- (३) BOQ फाराममा आफूले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर फर्म/कम्पनीको छाप दस्तखत सहित खामबन्दी पेश गर्नुपर्नेछ। केरमेट गरेको दररेट BOQ मूल्याङ्कनमा समावेश गरिने छैन।
- (४) सार्वजनिक खरिद ऐन तथा प्रचलित कानूनको परिधिभित्र रही सबैभन्दा कम कबोल गर्ने फर्म/कम्पनीलाई छनौट गरिनेछ।
- (५) रीत नपुगी र म्याद नाघी आएका निवेदन उपर कारबाही हुने छैन।
- (६) दररेट पेश गर्ने अन्तिम दिन सार्वजनिक विदा पर्ने गणमा कार्यालय खुल्ने अर्को दिन कार्यालय समयभित्र दररेट पेश गर्न सकिनेछ।

"व्यावसायिक र सिर्जनशील प्रशासन : विकास, समृद्धि र सुशासन"

परमानन्द शर्मा
नि. प्रमुख प्रशासकीय अधिकृत

BILL OF QUANTITY

Name of Project :- Radhakrishna Ma. Vi. School Building Construction and Maintenance Works at Shikhar- 5
F.Y. :- 2082/083

S.No.	Description of work	Unit	Quantity	Rate in figure	Rate in Word.	
1	Supply, mixing, placing, compact and cure concrete in mixes RCC M20 (1:1.5:3) foundation, column, beam, slab and all other specified work from ground floor to roof at any height completed as per drawing, specification and approval of A/E	cum	4.759			
2	Supply, fabricate, place and fix plywood/steel form work for RCC works including nails staging/supports, labour, lead and lift at any height removal and disposal as per drawing, specification and approval of A/E.	Sqm	40.936			
3	Supply, cut fabricate, place and tie, ribbed high tensile reinforcement steel bars including cost of 18 gauge black annealed binding wire, including steel and concrete chair and supports all the complete as per drawings, specification and approval of A/E.	KG	533.440			
4	Providing and laying brick masonry using first class local chimney burnt bricks with cement sand mortar 1:6 including scaffolding, curing, filling, cleaning and racking out mortar joints making ducts, recesses where required including all materials, labour, lead and lift all complete as per drawing, specification and approval of A/E.	cum	9.799			
5	Fabrication of steel Railing with 3 row of steel pipe (2 1/2" / 1" with support 1.5" steel pipe)	RF	91.000			
6	Supply, mixing, placing, 12-20 mm thick cement sand plaster (1:4) at slab, staircase, column and outer part of the building at any height completed including cost of scaffolding, material, labour, curing as per drawing, specification and approval of A/E.	Sqm	277.587			
7	Supply and applying one coat primer and two or more coats of plastic emulsion paints approved brand and colour over plastered surface at any level finished smooth and uniform shaded including watering preparation of base, cost of scaffolding, material, lab	Sqm	277.587			
8	Providing, fabricating and fixing in position mild steel grill made with required MS flats, strips, bars fabricated as per drawings, fixing in position using approved fasteners including 2 coat of enamel and primer base coat, etc., all complete as detailed in drawing, specification and instructions of the Engineer.	Sqm	28.414			
9	1.0 Supplying of material, preparation of 30mm x75mm size Local wood frame and 12mm thick waterproof plywood flush door shutter as per drawing fixing in position all complete.	Sqm	14.707			
10	Collapsible Gate	Sqm	10.400			
	Total Amount					
	VAT@13%					
	Total Amount with VAT					

Name of Contractor:-

Name of Firm:-

Signature:-

Seal:-